

Question and Answers – BAA 06-030

1.) Is there an incumbent contractor for this requirement? If so, could you please provide the contractor name, contract number, value, duration, and award date.

No, there is no incumbent contract or contractor for this particular effort.

2.) Vertical separation is said to be a maximum 15 feet. Is that a nominal measurement or the maximum in a seaway?

The 15 feet vertical separation is a nominal difference between the potential sending and receiving deck heights. The stated maximum vertical separation is while both platforms are at a level, still-water condition and does not take into account ship motions.

3.) Is it so that the ramp should be stowed and carried by the MLP or could it be either on the LMSR or on the MLP?

As stated in the BAA, the notional CONOPS is to have the ramp stowed on the MLP. However, the ramp should be capable of meeting the stowage requirements listed in the BAA regardless of which platform on which it is stowed.

4.) If testing with NSWCCD, can it be stated in the proposal that ONR will send money to Carderock for testing?

The use of government labs is encouraged. If the proposal calls for funding to be sent directly to a government facility by ONR for Phase I, then the amount of funding to be provided should be stated in the Phase I cost proposal.